



CHARLES MOSER
Vice Chairman - Drummond Island

JEREMY K. GAGNON
Chairman - Sault Ste. Marie

KEVIN E. SPRAGUE
Member - Sault Ste. Marie

BRIAN DECKER
Office Manager

ROBERT LAITINEN, P.S.
Manager

STEPHANIE BOILEAU, PE
Engineer

KEITH ERICKSON
Road Superintendent

REQUEST FOR BIDS

CHIPPEWA COUNTY BOARD OF ROAD COMMISSIONERS
3949 S. MACKINAC TRAIL
SAULT STE. MARIE, MI 49783

May 08, 2023

The Chippewa County Road Commission will accept sealed bids until 1:00 p.m. on Wednesday May 24, 2023 for gravel crushing at three locations within Chippewa County. All bids received will be publicly opened, read and tabulated at that time. Please submit your bid to the Road Commission office located at 3949 S. Mackinac Trail, Sault Ste. Marie, MI 49783.

Bids submitted for consideration are to be in sealed envelopes and plainly marked "Gravel Crushing bid". Any bids received after the specified date and time will be returned unopened. **FAXED BIDS WILL NOT BE ACCEPTED.**

All prices shall include stockpiling at the designated site within Chippewa County, Michigan.

Bid specifications can be obtained at the above address or by calling (906) 635-5295. Office hours are Monday through Friday, 6:00 a.m. to 4:00 p.m.

Bids shall become effective upon award.

The Chippewa County Road Commission reserves the right to accept or reject any or all bids, waive irregularities in any bid, and award the bid which, in their opinion, is in the best interest of the Road Commission.

CHIPPEWA COUNTY BOARD OF ROAD COMMISSIONERS
Jeremy K. Gagnon, Chairman
Charles Moser, Vice Chair
Kevin E. Sprague, Member

CHIPPEWA COUNTY ROAD COMMISSION

SPECIFICATIONS FOR AGGREGATE CRUSHING

Crush the annual aggregate requirements for the Chippewa County Road Commission at various locations throughout the County. The Commission shall provide the pits or pay the royalty, cross-section the stockpile, and require a minimum of 5,000 cu. yards per set up. The contractor shall provide all equipment and labor to crush and stockpile the aggregate. The contractor shall bid a unit price per cu. yard of the following:

1" Aggregate MDOT 22A

INSTRUCTION RELATIVE TO SUPPLYING

DENSE GRADED AGGREGATE

Materials specified hereunder are to be furnished to the Chippewa County Road Commission at the prices noted and stockpiling in accordance with the "Special Conditions" listed below.

At least ten days prior to the start of production. The supplier or producer is to contact the Chippewa County Road Commission for exact stockpile location. Alternate locations may be authorized if approved by the Road Commission in writing.

No aggregate shall be produced prior to notification of the Chippewa County Road Commission.

All material is to be tested in accordance with the Michigan Department of Transportation Maintenance Specifications for 22A. Material not in compliance with the MDOT 22A specification shall not be paid for.

All measurements will be taken under the supervision of the Chippewa County Road Commission Surveyor.

When stockpiles are called for at more than one delivery point, each pile should be completed and shaped prior to moving to the next site.

The Chippewa County Road Commission shall certify the material as tested approved and verify the measured quantities with the supplier or producer.

CHIPPEWA COUNTY ROAD COMMISSION

SUPPLEMENTAL SPECIFICATIONS FOR AGGREGATE CRUSHING

Description:

This work shall consist of producing, delivering, and placing aggregate in stockpiles at locations as designated above.

Stockpiling:

Aggregate shall be stockpiled in at least 2 or more layers not to exceed 4 foot each and in an approved manner such that segregation is avoided.

Measurement:

Aggregate will be measured in cubic yards by measurement in stockpiles.

The stockpile shall be uniformly shaped by the vendor to facilitate measurement and volumetric calculations.

If the conditions of measuring in stockpiles are not met the Road Commission will determine the necessary corrections. Any additional expense will be the vendor's responsibility.

Payment

The completed work as measured for aggregate crushing will be paid for at the contract unit price for the measured pay quantity in cubic yards. The pay quantity at each delivery point must be within plus or minus 5 percent of the purchase order quantity. Aggregate in excess of plus 5 percent will not be paid for unless approved by the Road Commission.

AGGREGATE CRUSHING 2023

<u>Pit Name</u>	<u>Location</u>	<u>Quantity Required</u>	<u>Unit Price</u>
Soo	Sec 24, T47N, R01W	10,000 cyd 22A	_____
Thornton	Sec 5, T42N, R03E	15,000 cyd 22A	_____
Greymont	Sec 24, T44N, R07W	15000 cyd 1" minus	_____
Production at this site is pure stone from existing waste rock piles at Greymont's eastern portal location. Setup location will have to be coordinated with Greymont staff.			
Drummond	Sec. 10 & 11 T41N, R05E	15000 cyd 1" minus	_____
Production at this site is pure stone from existing cap rock waste piles at Carmeuse's Drummond Island Quarry. Setup location will have to be coordinated with Carmeuse Staff.			

Submitted By

Name _____

Address _____

Phone _____

Signature _____

